

VIRGINIA PENINSULA REGIONAL JAIL
9320 MERRIMAC TRAIL
WILLIAMSBURG, VIRGINIA 23185
757-820-3902
Date: March 12, 2025



Request for Proposals VPRJ 2025-002
Perimeter Security Fencing & Installation

ADDENDUM 2
Additional Non-Mandatory Site Visit
Tuesday March 18th 10:00 AM -11:30 AM

Scope Specification Changes

Page 5

1. Tree Service Work:
 - a. Trees within ~~ten (10)~~ feet of the proposed work area are to be removed, haul away and/or chipped and blown outside the proposed work area.
Correction: Trees within a minimum of 15 feet of the proposed work area are to be removed, haul away and/or chipped and blown outside the proposed work area.

Page 5

2. Fencing Removal & Installation:
 - b. Install 12' high x 6 gauge galvanized with openings of ~~2 1/2" x 2 1/2"~~ twisted (barb) selvage chain-link fence on the perimeter of the facility.
Correction: Install 12' high x 6 gauge galvanized with openings of 2" x 2" twisted (barb) selvage chain-link fence on the perimeter of the facility.
 - c. Install 10' high x 6 gauge galvanized with openings of ~~2 1/2" x 2 1/2"~~ twisted (barb) selvage chain-link fence between the housing units.

Correction: Install 10' high x 6 gauge galvanized with openings of 2"x 2" twisted (barb) selvage chain-link fence between the housing units.

- d. All vertical poles to be schedule 40 x 3" galvanized and installed in the earth with 3000 psi concrete a minimum of 36". Poles to be 8' c/c. Addition: Terminal poles are to be 4" all others 3".

Page 6

3. Walk through gates:

- a. ~~Six (6) gates~~ with heavy duty galvanized hinges to be installed designated by COR.
Correction: Seven (7) gates with heavy duty galvanized hinges to be installed designated by COR.



Walk Through Gates X Seven (7)



Perimeter Fence